

23	Providing and fixing white vitreous china clay, flat back wash basin of size 630x450mm with pair of 15mm C.P. brass pillar taps with C.L/M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per the direction of Engineer-in-charge of the work.	Each	2.00	3600.0	Rupees Three Thousand Six Hundred Only
24	Providing and fixing white vitreous china clay, flat back wash basin of size 550x400mm with pair of 15mm C.P. brass pillar taps with C.L/M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per the direction of Engineer-in-charge of the work.	Each	2.00	3450.0	Rupees Three Thousand Four Hundred Fifty Only
25	Providing and fixing 600x450mm bevel lead edge mirror of superior glass with 6mm hard board backing and fixed to wooden cleats with C.P. crews, washers, including cost materials, labour complete as per the direction of Engineer-in-charge of the work.	Each	2.00	1285.0	Rupees One Thousand Two Hundred Eighty Five Only
26	Providing and fixing sand cast iron trap of 100mm dia, of self cleaning design with screwed down or hinged grating with or without vent arm including cutting and making good the walls and floors, cost of materials, labour, testing, complete as per the direction of Engineer-in-charge of the work.	Each	5.00	805.0	Rupees Eight Hundred Five Only
27	Providing vulcanizing or rubber float of approved 1st quality and make conforming to ISI Specifications and fixing for low down cistern as directed. Rate includes cost of materials and conveyance to work spot, complete as per the direction of Engineer-in-charge of the work.	Each	3.00	185.0	Rupees One Hundred Eighty Five Only
28	Providing wash basin brackets of approved 1st quality and make conforming to ISI Specifications and fixing for low down cistern as directed. Rate includes cost of materials and conveyance to work spot, complete as per the direction of Engineer-in-charge of the work.	Pair	2.00	225.0	Rupees Two Hundred Twenty Five Only
29	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia complete as per the direction of Engineer-in-charge of the work.	Each	5.00	159.0	Rupees One Hundred Fifty Nine Only
30	Providing stoneware gully trap of approved quality and make fixing in CC 1:2:4 and plastering with CM 1:3 wherever necessary. (Rate includes cost of all materials, fixtures and lead). for 10cms x 10 cms complete as per the direction of Engineer-in-charge of the work.	Each	5.00	182.0	Rupees One Hundred Eighty Two Only
31	Providing and fixing CI Nahani Trap of approved make conforming to ISI specifications and construction of cistern in CC 1:2:4 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot) for 10 cms x 7.5cms complete as per the direction of Engineer-in-charge of the work.	Each	2.00	250.0	Rupees Two Hundred Fifty Only
32	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 25mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour, charges HOM of equipments complete as per the direction of Engineer-in-charge of the work.	Mts.	25.00	260.0	Rupees Two Hundred Sixty Only

Signature of the Contractor

Executive Engineer
Brihan Bangalore Mananagara
Dasarahalli Division, Bangalore

33	Providing and fixing in trenches galvanised / mild steel tubes (medium grade) 20mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour, charges HOM of equipments complete as per the direction of Engineer-in-charge of the work.	Mts.	25.00	182.0	Rupees One Hundred Eighty Two Only
34	Providing and fixing water meter with stop cock, jam nut, socket in G.I. pipe line including cutting and threading the pipe and making long screws including cost of all materials, labour, HOM of equipments and testing complete as per the direction of Engineer-in-charge of the work.	Set	2.00	1295.0	Rupees One Thousand Two Hundred Ninety Five Only
35	Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per the direction of Engineer-in-charge of the work.	Each	2.00	157.0	Rupees One Hundred Fifty Seven Only
36	Providing and fixing in position brass stop cock of approved quality 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per the direction of Engineer-in-charge of the work.	Each	2.00	155.0	Rupees One Hundred Fifty Five Only
37	Providing and fixing in position brass stop cock of approved quality 23mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per the direction of Engineer-in-charge of the work.	Each	5.00	156.0	Rupees One Hundred Fifty Six Only
38	Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per the direction of Engineer-in-charge of the work.	Each	2.00	583.0	Rupees Five Hundred Eighty Three Only
39	Providing and fixing in position brass ball valve high or low pressure with plastic float of approved quality 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per the direction of Engineer-in-charge of the work.	Each	2.00	585.0	Rupees Five Hundred Eighty Five Only
40	Providing and fixing in position 25mm nominal bore non-return valve vertical type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per the direction of Engineer-in-charge of the work.	Each	2.00	525.0	Rupees Five Hundred Twenty Five Only
41	Providing and fixing to wall, ceiling and floor, low-density polyethylene pipes 6.00KGF/sq.cm. working pressure 50mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM of equipments and testing complete as per the direction of Engineer-in-charge of the work.	Mts.	15.00	527.0	Rupees Five Hundred Twenty Seven Only
42	Providing and fixing to wall, ceiling and floor, low-density polyethylene pipes 6.00KGF/sq.cm. Working pressure 63mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor including cost of all materials, labour charges, HOM of equipments and testing complete as per the direction of Engineer-in-charge of the work.	Mts.	6.00	267.0	Rupees Two Hundred Sixty Seven Only


Signature of the Contractor


Executive Engineer

43	Providing and placing on terrace. Polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity) complete as per the direction of Engineer-in-charge of the work.	Nos.	1.00	8250.0	Rupees Eight Thousand Two Hundred Fifty Only
44	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions includes cost of materials, fixtures and conveyance to work spot etc, Do dia 32mm complete. complete as per the direction of Engineer-in-charge of the work.	Each	1.00	126.0	Rupees One Hundred Twenty Six Only
45	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per the direction of Engineer-in-charge of the work.	Sqm.	49.70	52.0	Rupees Fifty Two Only
46	Providing Supplying M.S. Strut Steel Fabrication Charges erection and fixing including one coat shop paint two coat enamel paint data Rate approved 90000 per MT complete as per the direction of Engineer-in-charge of the work.	Mts.	100.00	310.0	Rupees Three Hundred Ten Only
47	Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per the direction of Engineer-in-charge of the work.	Cum.	1.69	268.0	Rupees Two Hundred Sixty Eight Only
48	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road.complete as per the direction of Engineer-in-charge of the work.	Mts.	40.00	318.0	Rupees Three Hundred Eighteen Only
49	Providing and fixing to wall, ceiling and floor galvanised / mild steel tube 32mm dia nominal bore with fittings (medium grade weight 3.23 kg/mtr) B class including cost of all materials, labour, charges HOM of equipments and testing complete as per the direction of Engineer-in-charge of the work.	Cum.	59.29	341.0	Rupees Three Hundred Forty One Only
50	Providing and laying in position to required level or slope 150mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per the direction of Engineer-in-charge of the work.	Mts.	30.00	345.0	Rupees Three Hundred Forty Five Only
51	PVC Pipe 110 mm Dia 2.5Kgs per Sqcm complete as per the direction of Engineer-in-charge of the work.	Mts.	15.00	89.0	Rupees Eighty Nine Only
52	Filling available excavated earth (excluding rock) in sides of foundations up to plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead up to 50 m. and lift upto 1.5 m. including cost of all labour complete complete as per the direction of Engineer-in-charge of the work.	Cum.	1.69	119.0	Rupees One Hundred Nineteen Only

Signature of the Contractor



Executive Engineer



53	Constructing brick masonry inspection chamber 600x 600mm. and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I. cover with frame (light duty) 600x600mm internal dimensions, total weight of cover with frame to be not less than 38kg (weight of cover 23kg and weight of frame 15kg) R.C.C. top slab with cement concrete 1:2:4 mix 20mm and downsize granite metal, foundation concrete 1:5:10 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete complete as per the direction of Engineer-in-charge of the work.	Nos.	3.00	4400.0	Rupees Four Thousand Four Hundred Only
54	Providing and placing on terrace. Polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity) complete as per the direction of Engineer-in-charge of the work.	Each	1.00	8250.0	Rupees Eight Thousand Two Hundred Fifty Only

Handwritten signature

Signature of the Contractor

Handwritten signature
EXECUTIVE ENGINEER
 Bruhat Bangalore Mahanagara Palike
 Dasarahalli Division, Bangalore-560057

Signature of the Contractor

Executive Engineer